BRUHAT BANGALORE MAHANAGARA PALIKE

Dasarahalli Zone

Draft Tender Schedule(DTS)

Name of work:Improvements to Roads At Mallikarjuna Swamy Temple And Shreeshakthi Bhavana Surrounding Area In Ward No.13 Shettyhalli Sub Division

Sl No	Description of Work	Unit	Quantity as per Estimate	Quoted Rate	
				In Figures	In Words
1	KSR66 M200-12.3 Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. C. Prestressed / Reinforced cement concrete grade M-20 & above. MORTH Specification No. 202 (Page No.139/ Item No.18.19/ PWD SR 2018	Cum	7.20	1684.34	
2	KSRRB 300-3. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil involving , excavated surface levelled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification MORTH/ Chapter 3. (Page No. 143/ Item No. 19.1/ PWD SR 2018-19)	Cum	629.15	137.80	
3	Removing And Refixing stone slabs of drains and pointing in C.M (1:3) (Page No.27/ Item No.5.33/ PWD SR 2018-19)	Sqm	166.32	137.80	
4	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs. with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications (P.No 222,I.No 27.18	Cum	242.87	5509.33	
5	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200 including cost of materials, labour, HOM complete as per specificationsdo Wall & bottom thickness 15cm (I No-37.59.2,P No-271 PWD SR 2018-19)	Cum	45.85	7189.42	
6	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C workincluding straightening, cutting, bending, hooking, placing in position,lapping and / or welding wherever required, tying with binding wire andanchoring to the adjoining members wherever necessary complete asper design (laps, hooks and wastage shall not be measured and paid)cost of materials, labour, HOM of machinery complete as perspecifications.Specification No. KBS 4.6.3 (I No 28.8.2,P No-229 PWD SR 2018-19)	Tonne	2.91	72326.98	
7	Providing and fixing Precast RCC cover slabs of 100 mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement and pointing for joints 1:3 cement mortor including form work, lift charges curing and concretee finished surface on both sides etc,and complete as per the directions of Enginner in charges.(Data Rate)	Sqm	103.68	1615.00	

ಕಂಡಿಕೆ( ) ರಲ್ಲಿ ವಿವರಿಸಿರುವ ಅಂಶಗಳ ಬಗ್ಗೆ ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು (ದಾಸರಹಳ್ಳಿ) ರವರು ದೃಢೀಕರಿಸಿಕೊಳ್ಳುವ ಷರತ್ತಿಗ ಒಳಪಡಿಸಿ ಡಿ.ಟಿ.ಎಸ್ ಅನುಮೋದಿಸಿದೆ.

ಕರಡು ಟೆಂಡರ್ ಷೆಡ್ಯೂಲ್‌ನ್ನು ತಿದ್ದುಪಡಿ ಮಾಡದಂತೆ ತಿದ್ದುಪಡಿ ಇಲ್ಲದೆ ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.

ತಿದ್ದುಪಡಿಗಳ ಒಟ್ಟು ಸಂಖ್ಯೆ:.....Nil.....

ರದ್ದುಗೊಳಿಸಿರುವ ಒಟ್ಟು ಐಟಂಗಳ ಸಂಖ್ಯೆ.....Nil.....

ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರು (ದಾಸರಹಳ್ಳಿ) ಧೀ

Scanned by CamScanner

Sl No	Description of Work	Unit	Quantity as per Estimate	Quoted Rate	
				In Figures	In Words
8	Providing and fixing Precast RCC slab of 250mm thick for Culverts made of Plain/Reinforced Cement Concrete design mix M25 with OPC@340kgs,with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregates@0.47cum,with superplasticizer@3lts confirming to 189103 1999 Reaffirmed 2008,Open Foundation complete as per Drawing and Technical Specification including cost of all materials, labour,HOM curing,form works,scaffolding and centering complete as per specifications and pointing for ljoints 1:3 cement mortar including form work,lift charges,curing and concrete finished surfaces on both sides etc,complete and as per the directions of Engineer in Charge. (Data Rate)	Sqm	9.36	3674.00	
9	KSRRB M200-24. Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceable and unserviceable materials seperately complete as per specifications. MORTH Specification No. 202 (Page No-140 Item no 18.47 of KPWD SR 2018-19)	Cum	65.88	952.94	
10	KSRRB 300-49. Scarifying bituminous course 50mm to 75mm thick along with premix carpet / surface dressing by manual means without disturbing the base and stacking of the debris materials including cost of all labour charges complete as per specifications. MORTH / Chapter 3 (Page No. 146/ Item No.19.55/ PWD SR 2018 19)	Sqm	798.00	95.40	
11	KSRRB M300- Construction of Embankment with Material Gravel/ Murrum. KSRRB M300-53. Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300 -2 complete as per specifications.(Including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of proctors density) MORTH Specification No. 305 (P.No. 148, I.No. 19.60 CSR 2018-19)	Cum	265.65	344.50	
12	KSRRB 300-Compaction KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications MORTH / Chapter 3 (Page No-147 Item no - 19.64 of KPWD SR 2018-19)	Cum	1564.60	6.36	
13	KSRRB M400-17. Providing, laying, spreading and compacting cushed stone aggregates of granite / trap I basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve thedesired density complete as per specifications. MORTH Specification No. 406 (Page No 158 Item no - 20.18 of KPWD SR 2018-19)	Cum	235.16	2001.28	

ಕಂಡಿಕೆ(9K) ರಲ್ಲಿ ವಿವರಿಸಿರುವ ಅಂಶಗಳ ಬಗ್ಗೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು (EE.....) ರವರು
ದೃಢೀಕರಿಸಿಕೊಳ್ಳುವ ಷರತ್ತಿಗ ಒಳಪಡಿಸಿ ಡಿ.ಬಿ.ಎಸ್
ಅನುಮೋದಿಸಿದೆ.
ಕರಡು ಟೆಂಡರ್ ಷೆಡ್ಯೂಲ್‌ನ್ನು ತಿದ್ದುಪಡಿ ಮಾಡದಂತೆ
ತಿದ್ದುಪಡಿ ಇಲ್ಲದೆ ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.
ತಿದ್ದುಪಡಿಗಳ ಒಟ್ಟು ಸಂಖ್ಯೆ:.....
ರದ್ದುಗೊಳಿಸಿರುವ ಒಟ್ಟು ಪಟಂಗಳ ಸಂಖ್ಯೆ.....

[illegible] ಅಭಿಯಂತರರು (ಮಾರಾಹಳ್ಳಿ) ಧೀ

Scanned by CamScanner

Sl No	Description of Work	Unit	Quantity as per Estimate	Quoted Rate	
				In Figures	In Words
14	Cement concrete pavement Construction of un reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with OPC cement or any other type as per clause 1051.2.2 design mix M20/M30 , with 25mm and down size graded granite metal coarse aggregates and fine aggregates , with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008 , mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications. - M30 (at 360Kg per cum coarse aggregate @ 0.69cum and fine aggregate @	Cum	380.55	5354.02	
15	Removal of Unserviceable Soil with Disposal KSRRB M300-19. Removal of unserviceable soil including excavation, loading and disposal but excluding replacement by suitable soil which shall be paid separately as per clause 300.5 complete as per specifications. MORTH Specification No. 301 (P.No.144 & I.No.19.20 PWD 18 19)	Cum	629.15	34.98	
16	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. MORTH -100/ Chapter 1 (P.No.136 & I.No.17.1 PWD 18 19)	Cum	124.95	57.00	
17	KSRRB M100-4.1. Cost of Haulage Excluding Loading and Unloading MORTH -100/ Chapter 1 Case I : Surface Road (P.No.136 & I.No.17.4 PWD 18 19)	t.km	754.10	25.60	

No of Corrections:

Executive Engineer
Dasarahalli Division
BBMP - Bangalore

DTS APPROVED

ಕಂಡಿಕೆ(24) ರಲ್ಲಿ ವಿವರಿಸಿರುವ ಅಂಶಗಳ ಬಗ್ಗೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು (ನಿರ್ವಾಹಕ) ರವರು
ದೃಢೀಕರಿಸಿಕೊಳ್ಳುವ ಪರತ್ತಿಗ ಒಳಪಡಿಸಿ ಡಿ.ಟಿ.ಎಸ್
ಅನುಮೋದಿಸಿದೆ.
ಕರದು ಬಿಂಡರ್ ಷೆಡ್ಯೂಲ್‌ನ್ನು ತಿದ್ದುವಡಿ ಮಾಡದಂತೆ
ತಿದ್ದುಪಡಿ ಇಲ್ಲದೆ ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.
ತಿದ್ದುಪಡಿಗಳ ಒಟ್ಟು ಸಂಖ್ಯೆ: ಶೂನ್ಯ
ರದ್ದುಗೊಳಿಸಿರುವ ಒಟ್ಟು ಐಟಂಗಳ ಸಂಖ್ಯೆ nil

ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರು, ದಾಸರಹಳ್ಳಿ ವಲಯ

Scanned by CamScanner